



BUREAU VERITAS

Ref. No: IND.B.7.2022.300DR-R3

**SOUNDNESS ASSESSMENT OF EXISTING AWHO CLUB HOUSE
BUILDING IN THE PREMISES OF
M/S ARMY WELFARE HOUSING ORGANIZATION,
KOCHI, KERALA.**

APRIL 2023



**BUREAU
VERITAS**

Move Forward with Confidence

BUREAU VERITAS INDIA PVT LIMITED

Head Office

72, Business Park Ground Floor,
Marol Industrial Area, MIDC Cross Road 'C',
Andheri (East), Mumbai- 400 093, India
Tel.: +91 22 6274 2000

Regional Office

1030, 13th Cross,
Banashankari 2nd Stage, Attimabbe Road
Bengaluru, India – 560070,
Tel.: 91 80 2698 0200

www.bureauveritas.co.in

**SOUNDNESS ASSESSMENT OF EXISTING AWHO CLUB HOUSE
BUILDING IN THE PREMISES OF M/S ARMY WELFARE HOUSING
ORGANIZATION,
KOCHI, KERALA.**



General View of AWHO Club House Structure



General View of AWHO Club House Structure

ACKNOWLEDGEMENT

We are thankful to the concerned authorities of M/s Army Welfare Housing Organization, Kochi, for their kind co-operation during the assessment. We appreciate the courtesy & support extended to the Bureau Veritas auditors.

- Bureau Veritas (India) Pvt. Ltd.

DISCLAIMER

This report includes the findings of the Site inspections carried out at Chanderkunj Army Towers of M/s Army Welfare Housing Organization. This report is issued within the scope of contract, documents submitted and does not perpetuate into compliance to any statutory regulations and / or codes of any country/region. The discussion of facts, as determined by the investigator, and the views expressed in the report do not assume and are not intended to establish the existence of any duty at law on the part of M/s Army Welfare Housing Organization, their employees or agents, contractors or any other party. This report neither determines nor implies liability. All the information provided in this report is based on the condition of site as on the date of audit/inspection and the information and access provided to the inspector. This report is only a third-party observation and is not a certificate of any assurance to any party regarding the future condition of the site. Under no circumstances shall Bureau Veritas (India) Pvt Ltd, its employees or the inspector shall be in any way responsible or liable for any accidents, incidents, damage to life, property or any other legal issue arising out of the site mentioned in this report directly or indirectly.

- Bureau Veritas (India) Pvt. Ltd

Report on	:	Soundness Assessment of existing AWHO Club House Building in the premises of M/s Army Welfare Housing Organization, Kochi, Kerala.
Report for	:	M/s. Army Welfare Housing Organization C/o Prasanna Vihar, Marine Drive, Opp. High Court, Kochi – 682 031.
Reference	:	Meeting on 13-10-2022
Period of Assessment	:	18 th March 2023 to 24 th March 2023
Assessment carried out under the guidance of	:	Mr. Mohankumar General Manager-South Asia Region-NDT & RR Dr. Shantharaju K Technical Advisor - Design review, NDT & RR Mr. R N Ravishankar Senior Manager – NDT & RR Mr. Avinash J Technical Manager-NDT & RR (PAN INDIA) Mr. Vijay H V Manager – NDT & RR Mr. Girish R Manager – NDT (South) M/s Bureau Veritas (India) Pvt Ltd Bangalore.
Assessment carried out by	:	Mr. Manjunath B S Engineer – Design Mr. Harish M Achari Asst. Manager - NDT Mr. Chethan H R Engineer – NDT Mr. Bibin Joy Engineer – NDT Mr. Sreenivasa M T

Senior Executive - NDT

Mr. Ramesh Raju
Executive - NDT

Mr. Ranjith P Menon
Senior Technician

M/s Bureau Veritas (India) Pvt Ltd,
Bengaluru & Kochi.

**Assessment carried out
in the presence of**

: Lt. Col. Sidhartha Singhal
Project Director
Army Welfare Housing Organization

Rear Admiral P Ashokan (Retd.)
President

Mr. Jaya Kumar Velloor
Manager

Residential Welfare Association (RWA)
Managing committee, Chanderkunj Army
towers, Kochi, Kerala.

Date of submission of final report : 30th April 2023

CONTENTS

Section	Topics	Page No.
1	INTRODUCTION	07
2	PHYSICAL OBSERVATIONS	07 - 08
3	INVESTIGATIVE TESTS	08 – 10
4	INFERENCES	10
5	RESTORATION MEASURES	10 – 11
6	CONCLUDING REMARKS	11
	<i>ANNEXURES</i>	
	TEST REPORT (SEMI-DESTRUCTIVE CORE COMPRESSIVE STRENGTH TEST)	01 - 01
	TEST REPORT (CHLORIDE & SULPHATE CONTENT)	01 - 01
	TEST REPORT (pH)	01 - 01
	TEST REPORT (ULTRASONIC PULSE VELOCITY TEST)	01 - 04
	TEST REPORT (REBOUND HAMMER TEST)	01 - 04
	TEST REPORT (COVER METER TEST)	01 - 03
	SKETCHES	01 - 05
	SPECIFICATIONS	01 - 01
	PHOTOGRAPHS	01 - 05

1.0 INTRODUCTION

The “AWHO Club House” structure/building located in the premises of M/s Army Welfare Housing Organization Kochi District, Kerala, is a conventional reinforced cement concrete framed structure with infilled masonry walls. The building comprises of ground and first floor only. Building was reported to be constructed about 07 years back since then it is in service.

The concerned authorities of AWHO wanted to ascertain the soundness of the existing building. In view of this the concerned authorities made a reference to M/s. Bureau Veritas to evaluate the soundness of the existing Club House building.

In response to this, a detailed investigative study involving visual inspection and various nondestructive and lab tests were carried out by us during 17th February 2023 to 18th February 2023 at site. This report, in brief, summaries the outcome of the test results, inference drawn, proposed restoration measures and conclusions made thereon.

2.0 PHYSICAL OBSERVATIONS

Following are the physical observations made consequent to detailed inspection of the above-mentioned building:

Ground Floor

- No signs of settlement in foundation system was observed in any part of the building.
- Minor separation cracks were observed at the junction of RC members and masonry wall at few locations.

(Refer Sketch DWG No. DM/ CH/ GF, 1F-01)

First Floor

- Peeling of paint, growth of fungus and damp patches were observed over the external masonry walls in staircase regions at several locations.
- Minor separation cracks were observed at the junction of RC members and masonry wall at several locations.

(Refer Sketch DWG No. DM/ CH/ GF, 1F-01)

Terrace Floor

- Cracks were observed in overhead tank wall at few locations.
- Stagnation of water were observed over the terrace flooring at few locations.
- Leakage of water was observed from RC overhead tank at isolated location.

(Refer Sketch DWG No. DM/ CH/ TF-02)

3.0 INVESTIGATIVE TESTS

In order to evaluate the soundness of the building, following investigative studies were resorted to:

1. Semi-Destructive Core test to assess the quality/ strength of in-situ concrete in identified RC members.
2. Non-destructive Ultrasonic Pulse Velocity test to assess the quality/ homogeneity of in-situ concrete.
3. Rebound Hammer test on RC members to assess the estimated strength of in-situ concrete nearer to the surface.
4. Cover meter studies to assess the cover provided to the rebars in RC members.

1. **Semi-destructive core test to assess the quality / strength of in-situ concrete in identified RC members.**

Semi-Destructive test such as core test was resorted to in order to assess the strength of in- situ concrete in first floor RC Column. One core sample was extracted from first floor RC Column.

The extracted core samples were subjected to compressive strength test after necessary trimming and capping as per the guidelines in IS: 516 (Part-4) 2018.

The results of Semi-Destructive core test indicate that the compressive strength of concrete in tested core extracted from identified RC Column is **25.2 N/sq.mm.**

ACCEPTANCE CRITERIA:

As per the clause 17.4.3 of IS: 456-2000 (Reaffirmed 2016), concrete in the member represented by a core test shall be considered acceptable if the average equivalent cube strength of the cores is equal to at least 85% of the cube strength of the grade of concrete specified for the corresponding age and no individual core have a strength less than 75%.

2. Non-destructive Ultrasonic Pulse Velocity test to assess the quality/ homogeneity of in-situ concrete.

Ultrasonic Pulse Velocity test was conducted on RC members in order to assess the quality of in-situ concrete. The test was conducted using “PUNDIT LAB+” (Portable Ultrasonic Non-Destructive Digital Indicating Tester) equipment from M/s. Proceq, Switzerland, as per the guidelines in Indian Standards IS:516-(Part-5/sec-1)-2018. Direct & Semi-Direct method of probing was adopted during testing.

From the results of the Ultrasonic Pulse Velocity test, it is inferred that the quality of concrete in the tested regions of RC members is found to be “**Good Concrete**” as per **IS:516-(Part-5/sec-1)-2018**. Results of the tests & quality grading reference chart are furnished in **Test Report**.

3. Rebound Hammer test on RC members to assess the estimated strength of in-situ concrete nearer to the surface.

Rebound Hammer test was carried out on the RC slabs at random and accessible regions to assess the surface hardness and strength of in-situ concrete. The test was conducted using Schmidt Rebound Hammer from M/s. Proceq, Switzerland as per the guidelines in Indian Standard **IS: 516 (Part-5/ Sec-4) : 2020**. The results of the tests are tabulated in **Test Report** and corresponding strength chart reference.

The results of tests indicates that, the estimated compressive strength of in-situ concrete in the tested RC members at tested locations is in the range of **22 N/mm² to 34 N/mm²**.

4. Cover meter studies to assess the cover provided to the rebars in RC members.

Cover meter studies were carried out on RC members at random, in order to assess the thickness of cover concrete. The test was conducted using **Profometer-5⁺** from M/s. Proceq, Switzerland as

per the guidelines in **BS 1881-204:1988** & as per manufacturer's manual. The results of the test are tabulated in **Test Report**.

From the results of the test, it is found that cover concrete provided to the rebars is adequate in most of the tested RC members.

4.0 INFERENCES

Following are the inferences drawn, based on the detailed physical observations, results of various Non-destructive tests:

1. Dampness/ damp patches/ growth of fungus and peeling of paint in masonry wall are mainly due to the constant spilling of water from overhead tank.
2. Separation cracks observed are due to dissimilar materials, improper filling of joints / not provided with mesh between masonry and RC members during construction stages. Further, thermal effects caused by expansion and contraction of building have aggravated the cracks.
3. Stagnation of water over terrace is mainly due to inadequate slope provided in WPC.
4. Cracks in plaster might be due to shrinkage effect.
5. From the results of the non-destructive ultrasonic pulse velocity test & rebound hammer test, it is inferred that the quality/strength of concrete in tested regions of RC members is found to be satisfactory.
6. From the results of covermeter studies, the cover provided to the rebars is adequate in most of the tested RC members.

5.0 RESTORATION MEASURES

a) Treatment for debonded / dampness/deteriorated plaster in masonry walls.

1. The deteriorated /debonded plaster on masonry walls shall be totally removed by gentle chipping.
2. The mortar joints shall be deeply raked for about 10 to 15 mm & repointed using CM 1:4 as per standard practice.
3. Re-plastering to be carried out using 1:4 cement mortar as per specification added with polypropylene fibres and cured as per standard practice.

b) Treatment for separation cracks between masonry walls and RC members.

1. Existing plaster in the region about 20 mm on either side of the crack should be removed and loose particles shall be cleaned using wire brush.
2. 'U' groove of 12 mm wide 6 mm deep shall be made all along the crack at the interface of masonry wall and RC member junction and cleaned.
3. Groove shall be filled with flexible sealant line tackseal/ Polysulphate sealant/ silicon sealant or any other equivalent.
4. Treatment should be carried out as per sketch.

(Refer Sketch DWG No. RM/01)

6.0 CONCLUDING REMARKS

The Existing "AWHO Club House" structure/building located at M/s Army Welfare Housing Organization Kochi District, Kerala, as it stands is structurally sound. However, minor distressed region of the building call for appropriate restoration measures as recommended above.

On carrying out the above-recommended restoration measures effectively under the guidance of experienced technical personnel and by an experienced agency, the distressed members of the structure will be rendered normal and serviceable.

Further, it is needless to emphasize that periodic maintenance of the structure should be strictly adhered to for effective functioning and life enhancement of the structure.

CHETHAN H R
Engineer- NDT

AVINASH J
Technical Manager-NDT & RR
(PAN INDIA)



ANNEXURES



TEST REPORTS

TEST REPORT



Test Order/Report No. BVIPL/CONCRETE CORE: KL/1907/4/2023
 Date of Receipt: 18-04-2023

Date: 18/04/2023

Page 1 of 1

ULR-TC636923000001030F

ARMY WELFARE HOUSING ORGANIZATION

C/o Prasanna Vihar, Marine Drive,
 Oppo.High Court, Kochi-682031

Mechanical Testing
Building Materials

TEST REPORT ON CONCRETE CORE TEST

Source Of Sample : Sample supplied by the Customer
 Contract No/Proposal No : 17671143/IND.B.7.2022.300DR-R3 DT.25.10.2022
 Customers Reference : B/03029/SSI/job Work/CHN/AWHO Dated 30-12-2022
 Project# : Structural Stability of Chanderkunj Residential Army
 Towers of Army Welfare Housing Organisation
 (AWHO) Located at Silver Sand Island, Vyttila, Kochi
 Kerala
 Members tested : RC Columns
 Date of Core Extraction : 03.03.2023
 Date of test : 09.03.2023
 Grade of Concrete# : M30
 Reason for Testing : To ascertain the quality/ strength of in-situ concrete
 Age of concrete : More than 28 days #
 Capping Materials Used : EP10 Hardner (Part A) & EP10 Base (Part B)
 From M/s Fosroc Conbextra
 Condition of Sample : Satisfactory
 Test Method : IS: 516 Part 4: 2018

Sl. No	ID#	Core length (l) (mm) ##	Core diameter (d) (mm)	Core Weight (kg)##	Max. failure load (kN)	Corrected Core comp. strength (N/sq.mm) ###	l/d Ratio	Correction factor for (l/d) ratio+	Corrected cylinder comp. strength (N/sq.mm)	Equivalent cube strength++ (N/sq.mm)	Type of failure
1	Club House RC Column 1-2/E First Floor	110.0	68.0	0.924	72.2	21.06	1.618	0.958	20.18	25.2	Typical Compressive Failure

Core length and core weight after trimming and capping

###After applying correction factor for diameter of core which is less than 100 mm (i.e. Corrected Core Comp Strength, = Core Comp Strength * 1.06) IS:516-Part 4 :2018, Clause : 8.4.1

+ For l/d ratio, correction factor= 0.11(l/d)+0.78 as per IS:516-Part 4:2018, Clause 8.4.2

++ Equivalent cube compressive strength = 1.25 x corrected cylinder compressive strength as per IS:516-Part 4:2018, Clause 8.4.2

As furnished by the customer

Note: 1. Any correction invalidates this report.



for **BUREAUVERITAS (INDIA) PRIVATE LIMITED**
Construction Services Laboratory

PRASANTHA KUMAR P.S
Manager-B&I



Report No.:BVIPL:HC:KL/1218/3/2023/1a
Test order dated: 11.03.2023

Date:23.03.2023
Page: 1 of 1

Army Welfare Housing Organisation
C/o Prasanna Vihar, Marine Drive,
Opp. High Court, Kochi – 682 031.

ULR-TC600623100004614F

CHEMICAL TESTING
Building Materials

CHEMICAL TEST REPORT ON HARDENED CONCRETE SAMPLES

Source of Sample : Samples supplied by the customer
Customer's Reference : Letter No. B/03029/SSI/Job Work/CHN/AWHO dated 30.12.2022
Condition of samples : Satisfactory
UIN No. : 23010898
No. of samples tested : 1(One)
Project # : Carrying out structural Assessment and Consultancy for Analysis, NDT, Retrofitting Scheme at AWHO Project SSI, Kochi
Period of test : 20.03.2023 to 23.03.2023
Test Method : IS: 14959 (Part II) 2001 (Reaffirmed 2021), BS:1881 (Part 124) – 2015

Sl. No.	Identification #	Name of Test		
		Chloride content - Acid Soluble		Sulphate as (SO ₃) (% by mass of cement in concrete mix)
		(% by mass)	(kg/cu.m) \$	
1	First Floor RC Beam (1-2/E) of Club House	0.0021	0.051	0.44
Requirements as per IS:456-2000 (Reaffirmed in 2021)		-----	For reinforced concrete or plain concrete containing embedded metal, max. acid soluble chloride content in concrete should not exceed 0.6 kg/cu.m.	Total water-soluble sulphate content as SO ₃ should not exceed 4% by mass of cement in the concrete mix.

\$ Chloride Content is Calculated by taking average density of Hardened Concrete as 2400 kg/Cu.m

As furnished by the customer

- Note:
1. The results relate only to the items tested.
 2. Report shall not be reproduced, except in full, without the written approval of the lab.
 3. Any correction invalidates this report.

for BUREAU VERITAS (INDIA) PRIVATE LIMITED
Construction Services Laboratory

END OF THE REPORT

Signature
23/03/2023
BHAGWAN. S
Assistant Manager - Chemical Lab





Report No.:BVIPL:HC:KL/1218/3/2023/1b
Test order dated: 11.03.2023

Date:23.03.2023
Page: 1 of 1

Army Welfare Housing Organisation
C/o Prasanna Vihar, Marine Drive,
Opp. High Court, Kochi – 682 031.

CHEMICAL TEST REPORT ON HARDENED CONCRETE SAMPLES

Source of Sample : Samples supplied by the customer
Customer's Reference : Letter No. B/03029/SSI/Job Work/CHN/AWHO dated 30.12.2022
Condition of samples : Satisfactory
UIN No. : 23010898
No. of samples tested : 1(One)
Project # : Carrying out structural Assessment and Consultancy for Analysis, NDT, Retrofitting Scheme at AWHO Project SSI, Kochi
Period of test : 20.03.2023 to 23.03.2023
Test Method : Laboratory Developed Method (BVIPL/CHEM/SOP/Concrete pH)

Sl. No.	Identification #	Name of Test
		pH
1	First Floor RC Beam (1-2/E) of Club House	13.54

As furnished by the customer

- Note:
1. The results relate only to the items tested.
 2. Report shall not be reproduced, except in full, without the written approval of the lab.
 3. Any correction invalidates this report.

for BUREAU VERITAS (INDIA) PRIVATE LIMITED
Construction Services Laboratory

Handwritten signature and date: 23/03/2023

BHAGWAN. S
Assistant Manager - Chemical Lab



****END OF THE REPORT****



TEST REPORT

Contract No – 17671143/1

ULR No – TC600623200000115F

Date of Receipt – 27/12/2022

Date of submission – 25th April 2023

M/s. Army Welfare Housing Organization

Page No. 01 of 04

C/o Prasanna Vihar, Marine Drive,

Opp. High Court, Kochi – 682 031.

RESULTS OF ULTRASONIC PULSE VELOCITY TEST NDT Building Materials Reinforced Concrete Structures

Project	:	Soundness Assessment of existing AWHO Club House Building in the premises of M/s Army Welfare Housing Organization, Kochi, Kerala.
Members tested	:	RC Columns, Beams & Slab
Period of test	:	17 th February 2023 to 18 th February 2023
Grade of concrete	:	M30*
Age of concrete	:	More than 28 days*
Test instrument	:	PUNDIT LAB+ (Portable Ultrasonic Non-destructive Digital Indicating Tester)
Make	:	M/s. Proceq, Switzerland
Test method	:	Direct & Indirect Method
Technical reference	:	a. Indian Standard IS: 516 (Part-5/Sec 1)-2018 b. Instrument manual furnished by M/s. Proceq, Switzerland

Sl. No.	Floor / Member Identification#	Grid Identification#	Average Pulse Velocity (Km/Sec)	Remarks
1	2	3	4	5
Ground Floor				Refer quality grading chart for in-situ concrete
1	RC Column	B2	3.75	
2		A4	4.45	
3		A6	5.15	
4		B7	4.22	
5		7C	4.47	
6		7D	4.83	
7		6E	4.91	
8		2D	4.91	
9		2C	4.54	
10		1D	3.80	

(Signature)

AVINASH. J
Technical Manager - NDT & RR



Contract No – 17671143/1
Date of Receipt – 27/12/2022

ULR No – TC600623200000115F
Date of submission – 25th April 2023
Page No. 02 of 04

Page No. 02 of 04

1	2	3	4	5
11	RC Column	1E	3.65	Refer quality grading chart for in- situ concrete
12	RC Beam	C/2-4	3.82	
13		B/3-4	3.82	
14		B/7-6	3.91	
15		D/6-7	3.91	
16		5/D-E	3.65	
17		1/D-C	3.19	
18		D/5-6	3.91	
19		RC Slab	C-B/2-4	
20	2-4/B-A		3.74 ⁺	
21	A-B/7-6		3.75 ⁺	
22	6-7/D-E		4.22 ⁺	
23	6-7/D-C		4.22 ⁺	
First Floor				
24	RC Column	7D	3.52	
25		6E	3.65	
26		2D	4.00	
27		1D	4.19	
28		E4	3.65	
29		2A	3.52	
30		6A	3.65	
31		B7	3.65	
32		C7	3.65	

(Signature)



Contract No – 17671143/1
Date of Receipt – 27/12/2022

ULR No – TC600623200000115F
Date of submission – 25th April 2023

Page No. 03 of 04

1	2	3	4	5
33	RC Column	2B	3.65	Refer quality grading chart for in- situ concrete
34	RC Beam	D/7-6	4.32	
35		E/2-3	4.12	
36		C’/1-2	4.10	
37		D/1-2	4.10	
38		C/4-5	3.80	
39		C/2-3	3.59	
40		RC Slab	D-E/7-6	
41	2-3/E-D		4.16 ⁺	
42	1-3/E-D		4.34 ⁺	
43	1-2/C’-D		3.81 ⁺	
44	2-1/A-B		3.79 ⁺	
Terrace Floor				
45	RC Overhead Tank	Column (left side)	4.23	
46		Beam (left side)	4.16	
47		Slab loc:1 (bottom)	3.70 ⁺	
48		Slab loc:2 (bottom)	3.84 ⁺	

#Refer sketch **DWG.REF.No GL/ CH/ GF, 1F-01 & GL/ CH/ TF-02** for Floor / Member / Grid Identification.

*As furnished by the customer.

Note-1:

+As per Clause 2.4.3.2.5 IS: 516 (Part-5/Sec1):2018, 0.5km/sec is been added to the reading above 3km/sec.

Note-2:

1. The results relate only to the sample tested.
2. Report shall not be reproduced, except in full, without the written approval of the lab.
3. The report shall be read in line with disclaimer given at rear side of the report.
4. Any correction invalidate this report.

(Signature)

REFERENCE QUALITY GRADING CHART FOR (ULTRASONIC PULSE VELOCITY TEST)

Instrument : PUNDIT [Portable Ultrasonic Non-Destructive Digital
Indicating Tester]

Make : M/s. Proceq, Switzerland

i) For Concrete ($\leq M25$)

Pulse Velocity (Km/sec)	Concrete Quality Grading
Below 3.5	Doubtful
3.5 to 4.5	Good
Above 4.5	Excellent

ii) For Concrete ($> M25$)

Pulse Velocity (Km/sec)	Concrete Quality Grading
Below 3.75	Doubtful
3.75 to 4.50	Good
Above 4.50	Excellent

Note: Concrete quality grading for different velocity criterion as reproduced from Table-1 of IS 516 (Part 5/Sec1): 2018 Clause 2.5.2 Amendment November -2019.

In case of “Doubtful quality”, it may be necessary to carry out further testing.



TEST REPORT

Contract No – 17671143/2

ULR No – TC600623200000116F

Date of Receipt – 27/12/2022

Date of submission – 25th April 2023

M/s. Army Welfare Housing Organization

Page No. 01 of 04

C/o Prasanna Vihar, Marine Drive,

Opp. High Court, Kochi – 682 031.

RESULTS OF REBOUND HAMMER TEST

Project	:	Soundness Assessment of existing AWHO Club House Building in the premises of M/s Army Welfare Housing Organization, Kochi, Kerala.
Members tested	:	RC Columns, Slab & RC wall.
Period of test	:	17 th February 2023 to 18 th February 2023
Grade of concrete	:	M30*
Age of concrete	:	More than 28 days*
Test instrument	:	Schmidt Hammer
Make	:	M/s. Proceq, Switzerland
Position of hammer	:	Vertically upwards
Technical references	:	1. Indian Standard IS: 516(Part 5/Sec 1):2020 2. Instrument manual furnished by M/s. Proceq, Switzerland

NDT
Building Materials
Reinforced Concrete Structures

Sl. No.	Floor / Member Identification#	Grid Identification#	Average Rebound Number ⁺	Remarks
1	2	3	4	5
Ground Floor				Refer reference chart for estimated compressive strength range of in-situ concrete
1	RC Column	B2	22	
2		A4	24	
3		A6	24	
4		B7	22	
5		7C	24	
6		7D	24	
7		6E	24	
8		2D	22	
9		2C	24	
10		1D	30	
11		1E	36	

AVINASH. J

AVINASH. J
Technical Manager, NDT & SR



Contract No – 17671143/2
Date of Receipt – 27/12/2022

ULR No – TC600623200000116F
Date of submission – 25th April 2023
Page No. 02 of 04

1	2	3	4	5	
12	RC Slab	C-B/2-4	26	Refer reference chart for estimated compressive strength range of in-situ concrete	
13		2-4/B-A	26		
14		A-B/7-6	26		
15		6-7/D-E	30		
16		6-7/D-C	30		
First Floor					
17	RC Column	7D	24		
18		6E	26		
19		2D	24		
20		1D	30		
21		E4	26		
22		2A	28		
23		6A	26		
24		B7	26		
25		C7	26		
26		2B	24		
27	RC Slab	D-E/7-6	38		
28		2-3/E-D	34		
29		1-3/E-D	34		
30		1-2/C'-D	36		
31		2-1/A-B	28		
Terrace Floor					
32	RC Overhead Tank	Column (left side)	20		
33		Beam (left side)	30		



Contract No – 17671143/2
Date of Receipt – 27/12/2022

ULR No – TC600623200000116F
Date of submission – 25th April 2023

Page No. 03 of 04

Refer sketch **DWG.REF.No GL/ CH/ GF, 1F-01 & GL/ CH/ TF-02** for Floor / Member / Grid Identification.

+ After applying necessary correction factor for impact position of Hammer.

*As furnished by the customer.

Note-1:

The estimation of strength of concrete by rebound hammer method cannot be held to be very accurate and probable accuracy of prediction of concrete strength in a structure is $\pm 25\%$.

Depending upon correlation curve and methodology adopted for establishing correlation between rebound index and likely compressive strength as per clause 8.1 of IS 516 (Part5/Sec4):2000.

Note-2:

1. The results relate only to the sample tested.
2. Report shall not be reproduced, except in full, without the written approval of the lab.
3. The report shall be read in line with disclaimer given at rear side of the report.
4. Any correction invalidate this report.

AVINASH. J
Technical Manager - NDT & RR

REFERENCE STRENGTH CHART FOR REBOUND HAMMER TEST

Test instrument : Schmidt Hammer
Make : M/s. Proceq, Switzerland
Type : N-34
Technical reference : 1. IS 516 (Part 5/Sec4): 2020
2. Instrument manual furnished by
M/s. Proceq, Switzerland

REBOUND NUMBER	ESTIMATED COMPRESSIVE STRENGTH RANGE (N/Sq.mm)
22 to 26	10 to 14
26 to 30	14 to 18
30 to 34	18 to 22
34 to 38	22 to 26
38 to 42	26 to 30
42 to 46	30 to 34

Note :

- Estimated compressive strength is worked out based on the Calibration Chart developed for the above test instrument in our laboratory.
- The estimation of strength of concrete by rebound hammer method cannot be held to be very accurate and probable accuracy of prediction of concrete strength in a structure is $\pm 25\%$. Depending upon correlation curve and methodology adopted for establishing correlation between rebound index and likely compressive strength as per clause 8.1 of IS 516 (Part5/Sec4):2000.



TEST REPORT

Contract No – 17671143/3

ULR No – TC600623200000117F

Date of Receipt – 27/12/2022

Date of submission – 25th April 2023

M/s. Army Welfare Housing Organization

Page No. 01 of 03

C/o Prasanna Vihar, Marine Drive,

Opp. High Court, Kochi – 682 031.

RESULTS OF COVER METER STUDIES

Project	: Soundness Assessment of existing AWHO Club House Building in the premises of M/s Army Welfare Housing Organization, Kochi, Kerala.
Members tested	: RC Column, Beam & Slab
Period of test	: 17 th February 2023 to 18 th February 2023
Test Instrument	: Profometer 5+
Make	: M/s Proceq, Switzerland
Technical Reference	: BS: 1881-(Part 204)-1988 and Test Instrument Manual "Metal & Reinforcement Detector" from M/s Proceq, Switzerland

NDT
Building Materials
Reinforced Concrete Structures

Sl. No.	Member / Floor Identification [#]	Grid Identification [#]	Range of Cover Concrete(mm) ⁺
1	2	3	4
Ground Floor			
1	RC Column	B2	34 to 55
2		A4	30 to 50
3		A6	39 to 45
4		B7	40 to 49
5		7C	40 to 52
6		7D	38 to 51
7		6E	39 to 53
8		2D	39 to 50
9		2C	42 to 51
10		1D	38 to 50
11		1E	39 to 52
12	RC Beam	C/2-4	30 to 40
13		B/3-4	30 to 35

(Signature)
Technical Manager - NDT & RR



Contract No – 17671143/3

Date of Receipt – 27/12/2022

ULR No – TC600623200000117F

Date of submission – 25th April 2023

Page No. 02 of 03

1	2	3	4
14	RC Beam	B/7-6	28 to 32
15		D/6-7	26 to 37
16		5/D-E	23 to 37
17		1/D-C	26 to 40
18		D/5-6	29 to 39
19	RC Slab	C-B/2-4	18 to 28
20		2-4/B-A	18 to 26
21		A-B/7-6	18 to 28
22		6-7/D-E	16 to 24
23		6-7/D-C	16 to 26
First Floor			
24	RC Column	7D	39 to 49
25		6E	38 to 50
26		2D	39 to 48
27		1D	35 to 45
28		E4	32 to 40
29		2A	32 to 59
30		6A	33 to 51
31		B7	31 to 57
32		C7	30 to 51
33		2B	35 to 55
34	RC Slab	D-E/7-6	15 to 20
35		2-3/E-D	16 to 20
36		1-3/E-D	15 to 24
37		1-2/C'-D	18 to 26
38		2-1/A-B	16 to 24

Signature

Technical Manager - NDT & RR



Contract No – 17671143/3
Date of Receipt – 27/12/2022

ULR No – TC600623200000117F
Date of submission – 25th April 2023
Page No. 03 of 03

1	2	3	4
39	RC Beam	E/2-3	24 to 37
40		C'/1-2	25 to 40
41		D/7-6	27 to 37
42		D/1-2	26 to 39
43		C/4-5	26 to 37
44		C/2-3	27 to 40

Refer sketch **DWG.REF.No GL/ CH/ GF, 1F-01 & GL/ CH/ TF-02** for Floor / Member / Grid Identification

+ Inclusive of Plaster.

*As furnished by the customer.


Note:

1. The results relate only to the sample tested.
2. Report shall not be reproduced, expect in full, without the written approval of the lab.
3. The report shall be read in line with disclaimer given at rear side of the report.
4. Any correction invalidate this report.



AVINASH. J
Technical Manager - NDT & RR



SKETCHES




AWHO CLUB HOUSE-GROUND FLOOR




AWHO CLUB HOUSE-FIRST FLOOR

CLIENT	M/s ARMY WELFARE HOUSING ORGANISATION (AWHO) VYTILLA, KOCHI, KERALA	TITLE	EXISTING GROUND AND FIRST FLOOR RC COLUMNS, BEAMS AND MASONRY WALLS	DRAWN: RSKK	CHECKED: CHR/MBS	SCALE NTS	DATE 24-03-2023	REV.No. REV.01					
PROJECT STRUCTURAL EVALUATION OF AWHO CLUB HOUSE AT ARMY WELFARE HOUSING ORGANISATION "CHANDERKUNJ ARMY TOWERS" AT SILVER SAND ISLAND, VYTILLA, KOCHI, KERALA				APPROVED: AJ/Dr.KS		DWG. REF. No :GL/CH/GF,1F-01		CONTRACT NO 17671143					




CLIENT	M/s ARMY WELFARE HOUSING ORGANISATION (AWHO) VYTILLA, KOCHI, KERALA	TITLE	EXISTING TERRACE FLOOR PLAN					DRAWN: RSKK	CHECKED: CHR/MBS	SCALE NTS	DATE 24-03-2023	REV.No. RO
	PROJECT STRUCTURAL EVALUATION OF AWHO CLUB HOUSE AT ARMY WELFARE HOUSING ORGANISATION "CHANDERKUNJ ARMY TOWERS" AT SILVER SAND ISLAND, VYTILLA, KOCHI, KERALA											
		CONSULTANTS <div>BUREAU VERITAS (INDIA) PVT. LTD. # 1030, 10th Cross, Banashankari 2nd Stage, Bangalore - 560 070. Tel. : 080-25802000</div>										CONTRACT NO 17671143



LEGEND:

- ▨ EFFLORESCENCE/DAMPNESS/DAMP PATCHES/PEELING OF PAINT.
- ▨ PLASTERING CRACKS IN RC BEAM/RC WALL
- ▨ SEPERATION CRACKS BETWEEN RC BEAM AND MASONRY WALL
- ▨ SEPERATION CRACKS BETWEEN RC COLUMN AND MASONRY WALL

AWHO CLUB HOUSE-GROUND FLOOR



AWHO CLUB HOUSE-FIRST FLOOR

TITLE

DISTRESS LAYOUT OF GROUND AND FIRST FLOOR

CLIENT
M/s ARMY WELFARE HOUSING ORGANISATION (AWHO)
VYTILLA, KOCHI, KERALA

PROJECT
STRUCTURAL EVALUATION OF AWHO CLUB HOUSE AT ARMY WELFARE
HOUSING ORGANISATION "CHANDERKUNJ ARMY TOWERS" AT SILVER SAND
ISLAND, VYTILLA, KOCHI, KERALA

DRAWN: RSKK

CHECKED: CHR/MBS

APPROVED: AJ/Dt.KS

CONSULTANTS
BUREAU VERITAS (INDIA) PVT. LTD.
1100A, 11th Cross, Bangalore 2nd Stage, Bangalore - 560 078
Tel : 080-2680200


DATE
24-03-2023

SCALE
NTS

DWG. REF. No 5M/CH/GF,1F-01

CONTRACT NO
17671143



REV. No.
RO




LEGEND:

- EFFLORESCENCE/DAMPNESS/DAMP PATCHES/PEELING OF PAINT.
- PLASTERING CRACKS IN RC BEAM/RC WALL
- SEPERATION CRACKS BETWEEN RC BEAM AND MASONRY WALL
- SEPERATION CRACKS BETWEEN RC COLUMN AND MASONRY WALL

CLIENT	M/s ARMY WELFARE HOUSING ORGANISATION (AWHO) VYTILLA, KOCHI, KERALA	TITLE	DISSTRESS LAYOUT OF TERRACE FLOOR				DRAWN: RSKK	CHECKED: CHR/MBS	SCALE NTS	DATE 21-04-2023
	PROJECT						STRUCTURAL EVALUATION OF AWHO CLUB HOUSE AT ARMY WELFARE HOUSING ORGANISATION "CHANDERKUNJ ARMY TOWERS" AT SILVER SAND ISLAND, VYTILLA, KOCHI, KERALA	APPROVED: AJ/Dr.KS	DWG. REF. No : DM/CH/TF-02	REV.No. RO
			 CONSULTANTS BUREAU VERITAS (INDIA) PVT. LTD. # 103A, 10th Cross, Bengaluru - 560 075 Tel. : 080-26862000				CONTRACT NO 17671143			
			 OFFICIAL SEAL VERITAS							



TITLE		TREATMENT FOR SEPARATION CRACK			
CLIENT	M/S ARMY WELFARE HOUSING ORGANISATION (AWHO) VYTHILLA, KOCHI, KERALA	DATE	REV	DESCRIPTION	
		DRAWN: RSKK	CHECKED: CHR/MBS	SCALE: NTS	DATE: 24-04-2023
PROJECT	SOUNDNESS ASSESSMENT OF EXISTING AWHO CLUB HOUSE BUILDING IN THE PREMISES OF M/S ARMY WELFARE HOUSING ORGANIZATION, KOCHI, KERALA.	DESIGNED:	APPROVED: AJ	DWG. REF. No. RM/01	REV. No. R0
		CONSULTANT'S  BUREAU VERITAS (INDIA) PVT. LTD. # 1030, 13th Cross, Banashankari 2nd Stage, Bangalore - 560 075. Tel. : 080-26980200			CONTRACT NO 17671143



SPECIFICATIONS

SPECIFICATION FOR ELASTOMERIC SEALANT FOR SEPARATION CRACK

Type of sealant	: Two part elastomeric waterproof sealant
Tensile strength	: 1.50 to 1.70 N/sq.mm
Elongation	: 600 to 700 %
Movement accommodation	: ± 25 to 40%
Pot life	: Not less than 30 minutes
Full cure	: 7 to 10 days max. (as per manufacturer's specification)
Shore A hardness	: 18 to 23 at 25° C
Pressure resistance	: 6 to 8 m hydrostatic head
Application temperature	
Range	: 10° C to 50° C
Density	: 1.60 to 1.70 Kgs / litre
Solid content	: 100% (Max.)
Resistance of exposure	: Shall not degrade when exposed to Ultra-Violet radiation and weathering
Service condition	: i) Shall be resistant to abrasion ii) Shall be impermeable to water when sealed iii) Shall be non-corrosive type iv) Shall be non-toxic and food grade
Life	: Shall be durable for a minimum period of 5 years (Guarantee period)
Technical reference	: BS - 4254 - 1983 or equivalent
Available sources	: "Masterflex 472/474" from M/s. BASF India Ltd., Bangalore

"Dr. Fixit PU Sealant"

M/s. Pidilite Industries Ltd.

"Nitoseal PU – Polyurethen selant"

"Thioflex 600 – Polysulphide sealant"

"Nitoseal MS 600 – Hybrid Silyl Modified Polyether"

M/s. Fosroc Chemicals (India) Pvt. Ltd., Bangalore

or any equivalent



PHOTOGRAPHS

PHOTOGRAPHS




General View of Building




General View of Building


PHOTOGRAPHS



**View of Separation Cracks Between
Masonry Walls and RC Members**





**View of Plaster Cracks in RCC beam
along grid 1/C-D**




View of Peeling of paint and damp patches in masonry wall at stair case regions


PHOTOGRAPHS



View of Separation Cracks Between Masonry Walls and RC Members




View of Cracks in OHT tank wall




View of Stagnation of water over the terrace flooring

PHOTOGRAPHS




View of Rebound Hammer test in progress



View of Ultrasonic Pulse Velocity test in progress

PHOTOGRAPHS



View of profometer (cover meter) test in progress